



SRRTEP - Western Committee ComEd Supplemental Projects

February 17, 2023

Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: ComEd-2022-006

Process Stage: Solutions Meeting 2/17/2023

Previously Presented: Need Meeting 11/18/2022

Project Driver:


Operational Flexibility and Efficiency

Specific Assumption Reference:

- Enhancing system functionality, flexibility, visibility, or operability

Problem Statement:

There are three 138 kV lines from Elmhurst to Franklin Park. Two of the lines share a ring bus circuit breaker at Franklin Park resulting in the loss of two of the three lines for a stuck breaker contingency.



Need Number: ComEd-2022-006

Process Stage: Solutions Meeting 2/17/2023

Proposed Solution:

Install a new 138 kV CB between Bus 4 and existing BT 2-4 to create a new bus 6

Estimated Transmission Cost: \$ 3.2 M


Alternatives Considered:

No feasible alternatives

Projected In-Service: 12/31/2023

Project Status: Conceptual

Model: RTEP 2027



Need Number: ComEd-2022-007

Process Stage: Solutions Meeting 2/17/2023

Previously Presented: Need Meeting 11/18/2022

Project Driver:


Customer Service

Specific Assumption Reference:

- Transmission System configuration changes due to new or expansion of existing distribution substations

Problem Statement:

ComEd Distribution has a need for an additional 138-12 kV transformer at Jefferson substation.



Need Number: ComEd-2022-007

Process Stage: Solutions Meeting 2/17/2023

Proposed Solution:

Install a new 138-12 kV transformer on bus 9 and move 138 kV Jefferson – Taylor line from bus 9 to Bus 8. Install 138 kV line breaker on 138 kV Jefferson – Taylor line.

Estimated Transmission Cost: \$ 4.5M

Alternatives Considered:

Install new 138-12 kV transformer on bus 8.


Estimated Transmission Cost: \$0

This alternative was not chosen because the new transformer would share a bus position with an existing transformer feeding the same distribution load resulting in reduced reliability.

Projected In-Service: 6/1/2023

Project Status: Engineering

Model: RTEP 2027



Appendix

High Level M-3 Meeting Schedule

| Assumptions | Activity | Timing |
|--|---|---|
| | Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| | Stakeholder comments | 10 days after Assumptions Meeting |
| Needs | Activity | Timing |
| | TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| | Stakeholder comments | 10 days after Needs Meeting |
| Solutions | Activity | Timing |
| | TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| | Stakeholder comments | 10 days after Solutions Meeting |
| Submission of Supplemental Projects & Local Plan | Activity | Timing |
| | Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| | Post selected solution(s) | Following completion of DNH analysis |
| | Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| | Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

Revision History

2/7/2022 – V1 – Original version posted to pjm.com